Roswell Road Transit and Streetscape Improvements August 18, 2022



Today's Presentation

- Project Area
- Need and Purpose
- Project Background
- Roswell Road Today
 - Project Area
 - Existing Conditions
- Proposed Concept
 - Concept Development Process
 - Key Features
 - Snapshots
- Next Steps









Project Area

- Project will **complete** the pedestrian network on Roswell Road south of I-285 within Sandy Springs.
- Total corridor length: 2.3 miles
 - Phase 1: 0.7 miles
 - Meadowbrook Drive (city limits) to Long Island Drive
 - Sidewalks on both sides of Roswell Road
 - Phase 2: 1.0 miles
 - Long Island Drive to Glenridge Drive
 - Sidewalks on the east side of Roswell Road
 - Phase 3: 0.6 miles
 - Glenridge Drive to I-285
 - Sidewalks on the east side of Roswell Road

Other Streetscape Projects

- T0033 CDBG Sidewalk/Streetscape
 - Phase 1 (completed)
 - Phase 2 (ROW acquisition)
- T0043 Roswell Rd/SR 9 at Glenridge Dr (substantially completed)




Need and Purpose

- The existing Roswell Road sidewalk infrastructure is **incomplete** and **substandard**
 - 75% of the T0019 project area lacks standard pedestrian facilities
- Multiple studies have been conducted in coordination with stakeholders that identify the need for sidewalk upgrades
- The purpose of the project is to complete the pedestrian network that serves MARTA transit users and provide total walk-up access to transit elements along Roswell Road
- Project benefits include:
 - Continuous ADA-compliant sidewalk along the Roswell Road corridor
 - Enhanced transit services by providing safe and clear access to MARTA bus stops
 - Street lighting for pedestrians
- Leads us to a baseline shoulder section of 2.5-ft curb & gutter, 5-ft landscape strip, and 8-ft sidewalk

Project Background

- 2007: Sandy Springs Comprehensive Plan
- 2008: Roswell Road Corridor LCI Study
- 2014: Bicycle, Pedestrian, and Trail Plan
- 2017: The Next Ten Comprehensive Plan
 - Roswell Road Small Area Plan
- **2019**: Funding authorized from the Surface Transportation Block Grant
 - Administered by the FTA through MARTA
- 2021: Begin concept design T0019





City of Sandy Springs Bicycle, Pedestrian and Trail Implementation Plan



DECEMBER 2014

HR





Roswell Road Today

Existing Conditions

- Inconsistent pedestrian facilities
 - Missing segments of sidewalk
 - Inadequate separation between pedestrians and vehicles
- Poor support to transit
 - Obscured MARTA bus stops
 - Lack of designated waiting areas



Proposed Concept

Concept Development Process

- Four site visits with City staff in the Fall of 2021
 - Walked the entirety of the project corridor
 - Documented substandard conditions
 - Established preferred sidewalk widths and locations
 - Site specific deviations to minimize impacts
- Bi-weekly status meetings
 - Continuous input from and communication with City staff
 - Multiple iterations as concept developed to minimize right-of-way (ROW) and utility impacts, determine wall locations, and accommodate MARTA bus shelters





Concept Development Process

- Data Collection
 - Topographic surveys
 - Subsurface Utility Exploration
 - Traffic Counts
 - Environmental Site Assessments
 - Survey coordination to establish property lines
- Concept Design
 - Prepared alignments per site visits and City staff input
 - Prepared concept level driveway, utility, and ROW impacts
 - Identified locations for landscaping and walls
 - Performed alternatives analysis on six segments
 - Coordinated with Stakeholders and related projects
 - Developed Opinion of Probable Construction Costs





Concept Development Process

- Traffic Engineering (TE) Analyses
 - Median Closure TE study confirmed feasibility of two raised medians
 - Segment 1: Meadowbrook Drive to Windsor Parkway
 - Segment 2: Peruca Place to I-285
 - Mid-block Pedestrian Crossing TE study recommends a signalized mid-block crossing to promote pedestrian safety
 - Agrees with T0070 Access Management Study
 - Warrant met between Lake Placid Drive and I-285





The Concept: Key Features





- Create continuous sidewalks along the corridor
 - Baseline design of 8-ft sidewalk, 5-ft landscape strip, and 2.5-ft curb & gutter
 - Deviations to baseline to minimize ROW and utility relocation impacts
- Establish continuous curb presence along corridor
 - Full curb and gutter where possible; header curb elsewhere
 - Establish grade and buffer separation between vehicles and pedestrians
- Marked crosswalks across all side streets
- **Raised medians** consistent with T0070 Access Management Plan and Median Closure TE study
- Concrete pads for bus shelters through coordination with MARTA





Before





After





Before






After





Before





After

Next Steps

Next Steps

- Public Comment
- Preliminary Design
- Final Design
- Construction

8/18/2022 - 9/16/2022 9/2022 - 7/2023 8/2023 - 12/2026 * 10/2024 - 3/2028 *

* Duration reflects staggering final design and construction over 3 phases

What We Need From You